



Zoning Resolution

THE CITY OF NEW YORK
Zohran K. Mamdani, Mayor

CITY PLANNING COMMISSION
Daniel R. Garodnick, Chair


99-22 - Special Height and Setback Regulations

File generated by <https://zr.planning.nyc.gov> on 2/20/2026

99-22 - Special Height and Setback Regulations

LAST AMENDED

12/5/2024



The underlying height and setback regulations applicable to a C5-1A District shall apply except as modified in this Section. The #street wall# location provisions of paragraph (a) of Section [35-631](#) shall apply to all #street# frontages. For #zoning lots# that do not contain #qualifying affordable housing# or #qualifying senior housing#, the gross area of each #story# located completely above a height of 170 feet shall not exceed 80 percent of the gross area of the #story# directly below it.