



Zoning Resolution

THE CITY OF NEW YORK
Zohran K. Mamdani, Mayor

CITY PLANNING COMMISSION
Daniel R. Garodnick, Chair


142-45 - Height and Setback for Shoreline Adjacent Lots in Subarea B1

File generated by <https://zr.planning.nyc.gov> on 2/17/2026

142-45 - Height and Setback for Shoreline Adjacent Lots in Subarea B1

LAST AMENDED

12/5/2024



In Subarea B1, as shown on Map 1 (Special Inwood District – Subdistricts and Subareas) in the Appendix to this Chapter, for #shoreline adjacent lots#, the height and setback regulations of Section [142-43](#) (Height and Setback for Sites in Subarea A2 With More Than 100 Feet of Shoreline) shall apply, except that paragraph (e) of such Section shall be modified to allow a tower to rise to a height of 265 feet, provided that the gross area of any #story# above 225 feet does not exceed 90 percent of the gross area of that #story# located directly below 225 feet. The #visual corridor# located between a line parallel to and 20 feet south of the prolongation of the centerline of West 218th Street and a line parallel to and 30 feet north of such centerline established by Section [142-60](#) (INWOOD WATERFRONT ACCESS PLAN) shall be treated as a narrow #street line# for the purposes of applying all height and setback regulations.