



Zoning Resolution

THE CITY OF NEW YORK
Zohran K. Mamdani, Mayor

CITY PLANNING COMMISSION
Sideya Sherman, Chair


32-351 - Ground floor use requirements in high-density areas

File generated by <https://zr.planning.nyc.gov> on 4/22/2026

32-351 - Ground floor use requirements in high-density areas

LAST AMENDED

6/6/2024



For all #Commercial Districts# mapped within, or with a #residential equivalent# of, R9 through R12 Districts, or #Commercial Districts# where the #floor area ratio# for #commercial uses# is greater than 10.0, the applicable #ground floor level# streetscape provisions of this Chapter shall apply, except that for #ground floor level# #street# frontages on #wide streets#, the alternative provisions for #Tier B street frontages# set forth in Section [32-322](#) shall not apply. However, the provisions of this Section shall not apply within any Special Purpose District.